

2026 Vegetation Management Program Plan

Sedgewater Energy Holdings | Vegetation Management | 2025-12-18

This plan sets the 2026 vegetation management program for Sedgewater Electric Delivery: cycle miles, resiliency acceleration, contractors, budget and standards. It was approved by the Director, Vegetation Management on December 18, 2025 and updates the vegetation management plan as required by December 31.

2026 program at a glance

Cycle trimming: 2,640 circuit miles.

Resiliency acceleration: 330 circuit miles on in-scope feeders.

O&M budget: \$31.4 million for the Vegetation Management department.

Contractors: four, one or two per district.

2025 results

Through November 30, 2025, contractors had completed 2,071.2 miles of the 2,215-mile 2025 cycle plan. The remaining December work and any carry-over will be reported in the 2025 vegetation management report due by May 1, 2026.

Cycle strategy

Sedgewater trims its overhead distribution circuits on a four-year cycle, about 2,215 miles a year of 8,860 overhead miles. The approved resiliency plan moves in-scope Bayou and Prairie feeders to a three-year cycle. Bayou's heavy tree canopy and Prairie's long overhead feeders drive most vegetation-caused interruptions.

Resiliency acceleration

The 2026-2028 Resiliency Plan, approved by the PUCT on October 23, 2025, includes vegetation cycle acceleration among its nine measures. A Texas resiliency plan may use hardening, modernization, undergrounding, vegetation management and other measures and must cover at least three years. The 330 acceleration miles in 2026 are scheduled after the cycle work on the same feeders so that crews do not return to a circuit twice in one season.

Contractors

Canopy Line Clearance Company works Harbor and Crossroads; Thornbury Vegetation Services and Oakmoss Utility Forestry work Bayou; Longleaf Right-of-Way Management works Prairie. Work units are issued by feeder and priced per mile.

Standards and clearances

Practices are measured against ANSI Z133.1, ANSI A300 and NESC Section 218. The company specification sets minimum clearances of 10 feet below, 10 feet to the side and 15 feet above primary conductors, with removal of overhanging limbs on resiliency feeders.

Reporting

Utilities must update the vegetation management plan by December 31 and file a vegetation management report by May 1 each year. This document is the 2026 plan update.